



Large Magnetic Field non-uniformity in nTMM environment at GP-SANS and its mitigation effort

Magnetic Field measurement performed around the magnet with Android S23 U Phone

Magnet 1 Box 7






$B_{tot}, \mu T$



Coordinate, inches



3-D point every
2" along the beam axis



B(total) in μT Magnet 1(7)



← *Ladder side*

Wall side →








B(total) in μT
Magnet 2(8)

← *Ladder side*

Wall side →




Visualizations for the Environmental Magnetic Field Measurements around the Magnets 1 & 2 at GP-SANS


Alina Moore 6.6.2025 – UTK n-n' Group

Field Component Plots from measurement tables

M1 (Guide 7)




M2 (Guide 8)




M1 Total Fields


Ladder Top




Wall Top



Ladder Low




Wall Low



Magnet 1

X - left/right
Y - Vertical
Z - Axial




Gif causes lower quality, see download links for mp4 and interactive versions


Scaling factor for visibility = 0.08

M2 Total Fields


Ladder Top





Wall Top



Ladder Low



Wall Low



Magnet 2

Max field = 805 uT


X - left/right
Y - Vertical
Z - Axial

Scaling factor for visibility = 0.08

Main problem:


Y component of M2's lower measurement paths

- Pointing to a beam below the magnets
- Seen in the Components for Magnet 2 low



- Same for wall side

Notice difference in magnitudes of exterior fields between both magnets



Scaling factor for visibility = 0.08

Downloads

- HTML interactive widgets
 - M1 https://drive.google.com/file/d/1gqCQmOwdoRJJ1-hSOob3vhPefNtpAO0w/view?usp=drive_link
 - M2 https://drive.google.com/file/d/1c5BuUtKv_T9Wuv6uZd_u8rjFt4o45bZt/view?usp=drive_link
 - Both https://drive.google.com/file/d/1pMvjZGdH9qwPyYvZUmR5k_Uh3BgyCKf3/view?usp=drive_link


- MP4 videos
 - M1 https://drive.google.com/file/d/1sE7O9vAeV9LSdpdP9beAHCaAld68vSbi/view?usp=drive_link
 - M2 https://drive.google.com/file/d/1libJzGokTBG9nXLUi1YicFSGmAJ3GaN0/view?usp=drive_link
 - Both https://drive.google.com/file/d/1dD_zm5KOksW5xh1Un04nV-_RMfDf3VH5/view?usp=drive_link

Major disturbance is coming from magnetized steel guide support piece (blue on picture) with surface field up to 30 G



FWHM of expected resonance ($V_F - \mu B = 0$) is ~ 0.17 Gauss
 Step in field scan $\text{FWHM}/6 \sim 0.03$ Gauss
 Scan region 25 – 27 Gauss, resonance peak expectation at ~ 26 Gauss
 In terms of current: from 0.32 A to 0.35 A with step 0.0004 A

Mag. field non-uniformity requirement < 0.03 Gauss
 Required suppression factor for 8 Gauss / 0.03 Gauss > 270
 Field non-uniformity expected in design < 0.1 Gauss
 and expected required suppression > 36




For the cylinder of mu-metal with diameter D , thickness T and rel. permeability $\mu (H)$
 theoretical transversal field suppression factor $S \approx \mu (H) \cdot T/D$
 longitudinal field suppression factor ~ 10 times worse


In the original design $T = 0.6 \text{ mm}$, $D = 8.5 \times 25.4 \text{ mm}$, μ depends on the external field / history
 For non-uniformity 0.1 Gauss $\mu > 50,000$ $S \sim 140$
 For non-uniformity 8 Gauss $\mu > 5,000$ $S \sim 14$

We need additional layer of magnetic shielding !


D.C. PERMEABILITY




Space available for additional mu-metal shield on both magnets



Al spine bar






PHYSICS
DIVISION

DIMENSIONS ARE IN INCHES
TOLERANCES UNLESS SPECIFIED:
ANGULAR: $\pm 0^\circ 30'$
TWO PLACE DECIMAL ± 0.01
THREE PLACE DECIMAL ± 0.003
SURFACE FINISH: 100 MICRO

	NAME	DATE
DRAWN	John C. Ramsey	Digitally signed by John C. Ramsey Date: 2025.06.09 06:17:15 -06'00'
CHECKED	Taylor Dodson	Digitally signed by Taylor Dodson Date: 2025.06.09 10:30:49 -04'00'
APPROVED	Yuri Kamyshkov	Digitally signed by Yuri Kamyshkov Date: 2025.06.09 16:58:00 -04'00'

nTMM@HFIR

Prototype Friday June 6 at UT





Expected schedule

- All construction materials are in hands and final drawings are ready
- Plan to finish construction at UT by Thursday June 12 evening
- Deliver parts to GP-SANS on Friday June 13 morning and perform installation during Friday
- Guides closing and pumping started next week (June 19 latest)
- Dry system run without neutrons with data for ~ 1 day after July 4